



WEBER MURPHY FOX

ARCHITECTURE INTERIORS CONSTRUCTION MANAGEMENT
LAND DEVELOPMENT AND PLANNING HISTORIC PRESERVATION

June 9, 2016

Re: 2015.170.00 - Lower Paxton Township Friendship Center

Information for Bidders:

Relamping of the fixtures in the Natatorium – The Owner will drain the pool if required for relamping the fixtures above it on Aug 28-Sept 3rd, 2016 ONLY (during the planned closing of the pool). The Contractor may relamp at his convenience **IF** approved safety measures permit alternate methods above the pool without requiring drainage.

LampSpecificationsFriendshipCommCenter01_04_2016 attached

MPE NOTES for drawings

- 1) CARDO STUDIO 112. PROVIDE A CIRCUIT FROM NEW RECEPTACLES TO EXISTING PANEL, CONNECT TO EXISTING 120 VOLT 20 AMP BREAKER OR PROVIDE NEW BREAKER AS REQUIRED.
- 2) STORAGE 113. PROVIDE A WALL BOX WITH CONDUIT UP TO ABOVE CEILING WITH BUSHING.
- 3) CARDO 112. PROVIDE CIRCUIT FOR NEW A/V SYSTEM. PROVIDE NEW CIRCUIT FROM A/V EQUIPMENT TO EXISTING PANEL, CONNECT TO EXISTING BREAKER OR PROVIDE NEW BREAKER AS REQUIRED. VERIFY POWER REQUIREMENTS WITH OWNER & A/V SUPPLIER. PROVIDE POWER TO AUTOMATIC SCREENS AS REQUIRED.
- 4) PROVIDE IN EXSITING BREAKER PNEL A NEW 30 AMP TWO POLE BREAKER AND CIRCUIT FOR NEW DRYER. Provide 2#10 & 1#10 GROUND COPPER WIRES.
- 5) CARDOR 112. PROVIDE MATERIALS AND LABOR TO RELOCATE LIGHTING FIXTURES AS SHOWN ON DRAWING A-300. COONECT TO EXSITING CIRCUITS AND CONTROLS.
- 6) CARDIO 112. PROVIDE NEW CIRCUIT FROM NEW 12' PADDLE CEILING FAN. EXTEND BACK TO EXISTING BREAKER PANEL. WIRE CONTROLS AS REQUIRED, LOCATE AS DIRECTED BY OWNER.

CONSULTANT

David V. Klinger, P.E.
Consulting Engineers
4101 Derry Street
Harrisburg, PA 17111-2244
717 561-1109 office

403 SOUTH ALLEN STREET, SUITE 115, STATE COLLEGE PA 16801
T: (814) 867-3508
F: (814) 867-3563
www.wmf-inc.com

WMF